



Response to Questions

TO THE PROSPECTIVE PROPOSERS UNDER RFB NO. 8358

Nicolaus Dairy Roadway


SACRAMENTO REGIONAL COUNTY SANITATION DISTRICT

The questions received and the answers to those questions are shown below:

- Question:** Will layout and staking be done by Regional San?
Answer: *No, this is responsibility of the contractor.*
- Question:** There is no information on what to do with dirt spoils. Will the dirt spoils be hauled off or kept on site?
Answer: *The dirt spoils from the over-excavation will be stockpiled at a location half a mile away on Bufferlands property as long as it is a clean fill. If there are any concrete debris, those would need to be hauled off.*
- Question:** Will Regional San do the compaction tests that are needed?
Answer: *Yes, Regional San or County inspectors will perform the compaction tests needed.*
- Question:** Is it ok to use recycled aggregate base?
Answer: *yes, as long as it meets Class 2 specification by Caltrans.*
- Question:** Will the construction trucks have access to site?
Answer: *The construction site is gated but during construction, the gates will be open for the work.*
- Question:** Who will inspect the materials?
Answer: *Regional San staff will inspect the materials and the delivery tickets for materials.*
- Question:** Please provide detail on wheelstops
Answer: *The drawings are revised to provide wheelstop details. Please see the revised drawings.*

8. **Question:** Please provide specification on cable for post and cable.
Answer: *The detail for posts are already included in drawings. For cable, 3/8-inch galvanized chain or braided wire would suffice.*
9. **Question:** Is there water available on site for construction work?
Answer: *Yes, there are construction wells and fill stations at SRWTP. Regional San staff will work with contractor to gain access to these fill stations.*
10. **Question:** Is there any construction staging area?
Answer: *Yes, the site has many areas where equipment and trucks can be parked as long as there is through access for other vehicles. Regional San staff will work with contractor to identify these.*
11. **Question:** Please verify the quantities for geotextile fabric.
Answer: *Please see revised quantities in the addendum and new bid-form.*
12. **Question:** Please verify the quantities for over-excavation and widening of the road from existing road.
Answer: *Please see revised quantities in the addendum and new bid-form.*
13. **Question:** Please provide the size, number and distance for the posts.
Answer: *The available posts outer diameter is approximately 4.5 in. We need 3 posts installed every 20 ft starting from the south concrete wall as one of the edges.*
14. **Question:** Is there any allowance for overexcavation resulting from proof rolling?
Answer: *No, there is no allowance for overexcavation. However, any additional work will be a change order.*
15. **Question:** Is the contractor responsible for tree removal?
Answer: *Yes, this work is included in the scope of work and as a bid item.*
16. **Question:** How do you want the tree removed?
Answer: *The tree is in the way of roadway design and needs to be completely removed along with the stump.*
17. **Question:** Is Pollution Liability Insurance required?
Answer: *No the Pollution Liability Insurance is not required for this project. Please see the addendum for revised language.*

Thank you,



Vyomini Upadhyay

Associate Civil Engineer